सम्मिश्र जांच दल/ Composite Trials Team द्वारा नेवी कार्यालय/ C/o Navy Office मुख्यालय/ Headquarter अन्डमान एवं निकोबार कमान/ Andaman & Nicobar Command पोर्ट ब्लेयर/ Port Blair - 744 102

CTT/300/11/03/TECH

03 Feb 23

The Commander-in-Chief {for CTO(Marine)} Headquarters Andaman and Nicobar Command Port Blair - 744 102

## **VIBRATION TRIALS OF STBD DA - INS CORADIVH**

- Vibration trials of STBD DA was undertaken on 01 Feb 23 at 40 Kw (50%) & 48 Kw (60%). The details of trials are placed at Enclosure.
- Observations. Following observed: -
  - (a) Vibration at Engine Free End Axial direction & Engine Drive End Horizontal direction at 50 % of rated load (40 Kw) found to be 14.9 mm/sec and 22.7 mm/sec respectively against limit of 16 mm/sec.
  - (b) Vibration at Engine Free End Axial direction and Engine Drive End Horizontal direction at 60 % of load (48 Kw) found to be 16.4 mm/sec and 25.8 mm/sec respectively against limit of 16 mm/sec.

(जगन्नाथ गूरुमूर्ति /Jagannath Gurumurthy) लेफ़्टिनेंट कमांडर / Lieutenant Commander उप-प्रभारी अधिकारी/ Dy. Officer-in-Charge क्रिते प्रभारी अधिकारी/ for Officer-in-Charge

Encl:- As Above

## Copy to.

The Naval Component Commander {for SSO (Tech)} Headquarters Naval Component c/o Navy Office Port Blair – 744 102 The Commodore Superintendent (for DSY) Naval Ship Repair Yard c/o Navy Office Port Blair – 744 102

The Commanding Officer INS Cora Divh c/o Navy Office Port Blair - 744 102

## Enclosure to CTT(PBR) letter CTT/300/11/03/TECH dated 03Feb 23

## **VIBRATION TRIAL REPORT - STBD DA**

1. <u>Vibration Trials</u>. Vibration trials were carried out at 50% and 60% of rated load on 01 Feb 23. Details of vibration trials are as follows: -

Ser.	Measuring Points	At 5	At 50% (40KW) load			0% (48 load	Remarks (Limit 16	
		V	Α	Н	V	Α	Н	mm/sec)
(a)	Engine free end	11	14.9	9.8	11.7	16.4	10.6	UNSAT
(b)	Engine drive end	6.5	3.9	22.7	8.6	3.9	25.8	
(c)	Alternator drive end	3.8	2.3	2.8	3.8	2.5	3.1	SAT
(d)	Alternator free end	5.1	3.0	1.9	5.3	3.5	1.7	