Tele 022-22751158

Naval Trials and Acceptance Authority

Fleet Mail Office Mumbai 400001

NATAA/300/ ASG

As per E-Sign

<u>Director/ Osl/C</u> – ETMA, MTU(Vzg), MTU(Mbi), HITU(Vzg), HITU(Mbi), ETMU(Vzg), ETT(Koc), ETMU(Kol), CTT(Pbr), HITU(Koc), HITU(Pbr),

#### TRIALS PROTOCOL FOR SHAFT GROUNDING SYSTEMS

- 1. Refer to IHQ MoD (N)/ ACOM (D&R) letter EG/ Policy/ TSC/ 02/ 22 dated 06 Jun 22 regarding Policy on Maintenance and Monitoring of Shaft Grounding System.
- 2. A detailed policy with respect to procurement, maintenance and monitoring of Shaft Grounding Systems (ASG/PSG) has been promulgated by IHQ MoD (N) vide letter ibid. The policy letter elucidates roles and responsibilities of various departments towards upkeep and maintenance of Shaft Grounding System on-board naval platforms. Further, coordinated and integrated trials by MTUs/ CTT, ETMA/ETMUs and HITUs are envisaged for holistic performance assessment of Shaft Grounding Systems during Pre/End of Refit trials and Commissioning trials.
- 3. Approved copy of the comprehensive Trials Protocol for Shaft Grounding Systems (ASG/PSG) is enclosed for necessary action by all concerned. MTUs/ CTT are requested to undertake trials of Shaft Grounding Systems as Lead Trial Agency and seek assistance of ETMA/ ETMUs/ HITUs as required. The Trial Reports are to be shared with respective HITUs for scrutiny and records.

Electronically Signed by: CDR RK PILLAI, 42208A

On 07-09-2022 16:41:25 Using login ID authentication through FMMS



**Enclosure**: - 1 - Trials Protocol of Passive Shaft Grounding System

2 - Trials Protocol of Active Shaft Grounding System

#### Copy to: -

The Flag Officer Commanding-in-Chief {for CEO/CLO/CCONO} Headquarters, Western Naval Command Mumbai 400001

The Commander-in-Chief {for CTO(Marine)} Headquarters, A&N Command c/o Naval Base Port Blair 744102 The Flag Officer Commanding-in-Chief {for CEO/ CLO/ CCONO} Headquarters, Eastern Naval Command Visakhapatnam 530014

The Flag Officer Commanding-in-Chief {for CEO/ CLO/ CCONO} Headquarters, Southern Naval Command Kochi 682004

Internal: - SO/ ACOM (D&R) DG NATAA

### TRIALS PROTOCOL - PASSIVE SHAFT GROUNDING SYSTEM

Note: The Shaft Ground System checks shall be undertaken in two phases namely Harbour (Installation Checks) and Sea (Functional Checks)

MAKE OF SHAFT GROUNDING SYSTEM/ OEM	
YEAR OF INSTALLATION	

### 1. **INSTALLATION CHECKS**.

SI.No	Component	Description/ Checks	TRIAL BY	SAT/ UNSAT	Observations/ Remarks
		Check for wearing and corrosion.			
(a)	Brushes	Contact with shaft (check any clearance using a feeler gauge).	MTU/ CTT		
		Check size of carbon brushes as per TDOI.			
		Check for corrosion or visual damage.			
(b)	Ring Assembly	Check passive ring is properly shorted with hull.	MTU/ CTT		
		Check for coating on the slip ring assembly as per technical manual (the coating material will depend on design and make).			
(c)	Voltmeter / Multi-	Check calibration certificate.	MTU/ CTT		
(-/	meter	Check for any fault indication.	SS		

## 2. **FUNCTIONAL CHECKS**. (By MTUs/CTT)

Sea Sortie	<u>Date</u>	<u>Time</u>	Port Shaft  Voltage Reading	Stbd Shaft  Voltage Reading
Sortie 1				
Sortie 2				

#### Notes:

- The functional checks of the system is to be undertaken by MTUs/ CTT (Pbr) during sea trials and a minimum of five readings are to be recorded at 30 – 60 mins intervals during two consecutive sailings and the recordings are to be corroborated with the design / previous recordings prior clearing the system.

#### TRIALS PROTOCOL - ACTIVE SHAFT GROUNDING SYSTEM

Note: The Shaft Ground System checks shall be undertaken in two phases namely Harbour (Installation Checks) and Sea (Functional Checks)

MAKE OF SHAFT GROUNDING SYSTEM/ OEM	
YEAR OF INSTALLATION	

## 1. **INSTALLATION CHECKS**.

<u>SI.No</u>	Component	<u>Description / Checks</u>	TRIAL BY	SAT / UNSAT	Observations / Remarks
		Check for wearing and corrosion.			
(a)	Brushes	Contact with shaft (check any clearance using a feeler gauge).	MTU/ CTT		
	C	Check size of carbon brushes as per TDOI.			
		Check for corrosion or visual damage.			
(b)	Ring Assembly	Check sensor ring is not shorted with hull.	MTU/ CTT		
	,	Check passive ring is properly shorted with hull.	WITO, CTT		
		Check power ring connectivity to power drive			
		Check insulation of all cables.			
(0)	Power Unit	Check power supply (input output wrt technical manual).	SS		
(c)	Power Offic	Check calibration of indication panel as per technical manual.	ETMA/ETMU		
		Check correct cable polarity of power ring cable and power ground.			

(d)	Multi-meter	Check calibration of fitted multi-meter.	SS/MTU/ CTT	
(e)	Local & Remote	Check correctness of indication.	SS/MTU/ CTT	
	Indications	Check for fault indications.		

# 2. **FUNCTIONAL CHECKS**. (By MTUs/CTT)

		<u>Time</u>	Port Shaft			Stbd Shaft				
Sea Sortie	<u>Date</u>		DC Shaft Voltage	AC Shaft Voltage	Output DC voltage	Output current	DC Shaft Voltage	AC Shaft Voltage	Output DC voltage	Output current
Sortie 1										
Sortie 2										

#### Notes:

- The functional checks of the system are to be undertaken by MTUs/ CTT during sea trials and a minimum of five readings are to be recorded at 30 – 60 mins intervals during two consecutive sailings and the recordings are to be corroborated with the design / previous recordings prior clearing the system.