Tele: 248306

सम्मिश्र जांच दल/ Composite Trials Team द्वारा नेवी कार्यालय/ C/o Navy Office मुख्यालय/ Headquarter अन्डमान एवं निकोबार कमान/ Andaman & Nicobar Command पोर्ट ब्लेयर/ Port Blair - 744 102

CTT/300/03/10/TECH

12 Jan 23

The Commander-in-Chief {for CTO (Marine)} Headquarters Andaman & Nicobar Command Port Blair - 744 102

#### RUNNING HOUR EXTENTION OF DA NO. 1 (250 KW) - IN LCU L52

- 1. Refer to HQANC letter ANC/42002/EG/10/3 dated 09 Nov 22.
- 2. <u>Background</u>. Running Hour Extention Trials including performance, vibration and attenuation checks of DA 1 onboard LCU L52 were undertaken on 11 Jan 23. DA was loaded upto 80%(200 KW) load on load bank and sustained for a duration of 02 hours.
- 3. <u>Performance Parameters</u>. A detailed report w.r.t engineering and performance trial is placed at **Enclosure**. The salient parameters are as follows: -
  - (a) <u>Lub Oil Pressure</u>. Lub oil pressure of DA at 80% of rated load was found to be 2.7 bar and is <u>SAT</u>.
  - (b) <u>Lub Oil Temperature</u>. Lub oil temperature of DA at various loads was found to be in the range of 72°C to 100°C and is <u>SAT</u>.
  - (c) <u>Fresh Water Temperature</u>. Fresh water temperature of DA was found to be in the range of 75°C to 88°C and is <u>SAT</u>.
  - (d) <u>Exhaust Temperature</u>. Exhaust temperature was observed to be 452°C at 80% of rated load (250 KW) and is <u>SAT</u>.
- 4. <u>Vibration Analysis</u>. Vibration trials were undertaken at 60% and 80% of rated load. Maximum vibration recorded was 9.0 mm/sec at 60% and 10.3 mm/sec at 80%, against the limit of 16 mm/sec.

## 5. Observations.

- (a) 80% load offered by SS.
- (b) Parameters not available in MCR remote panel.
- (c) Sea water pump safety guard not fitted.
- (d) Overflow line not connected in expansion tank.
- (e) Mounts are painted and not preserved.

- 6. Recommendations. In view of the above, the following are recommended:-
  - (a) Liquidation of defects/ observations mentioned at para 5 ibid.
  - (b) DA may be granted RH extension at 80% of rated load.

(जगन्नाथ गूरुमूर्ति /Jagannath Gurumurthy) लेफ़्टिनेंट कमांडर / Lieutenant Commander उप-प्रभारी अधिकारी/ Dy. Officer-in-Charge क्रिते प्रभारी अधिकारी/ for Officer-in-Charge

#### Copy to: -

The Naval Component Commander {for SSO (Tech)} c/o Navy Office Port Blair – 744 102

The Commanding Officer IN LCU L52 c/o Navy Office Port Blair – 744 102

## RUNNING HOUR EXTENTION OF DA NO. 1 (250 KW) - IN LCU L52

1. Trial Inspector

(a) Amit Kumar, ERA-3

(b) Ambesh, LME

2. Date and Time

11 Jan 22 (0930-1330 Hrs)

3. Equipment used for trials

(a) SPM T-30

(b) Temperature Gun

#### 4. Details of trials are as follows:-

## (a) Safety Device Checks.

| Ser.   | Description        | Unit               | Design<br>Value | DA 1<br>(250 KW) |  |  |
|--------|--------------------|--------------------|-----------------|------------------|--|--|
| (i)    | Low LO Pr Alarm    | Kg/cm <sup>2</sup> | 1.2             |                  |  |  |
| (ii)   | Low LO Pr Trip     | Kg/cm <sup>2</sup> | 0.8             | 0.8              |  |  |
| (iii)  | High FW temp Alarm | °C                 | 91              | 92               |  |  |
| (iv)   | High FW temp Trip  | °C                 | 97              | 96               |  |  |
| (v)    | High LO temp Alarm | °C                 | 119             | 119              |  |  |
| (vi)   | Over speed Trip    | RPM                | 1650            | 1650             |  |  |
| (vii)  | Crash stop Local   | _                  | Ops/ Non-ops    | Ops              |  |  |
| (viii) | Crash stop Remote  |                    | Ops/ Non-ops    | Ops              |  |  |


# (b) Performance Parameters at 80% Load.

| Ser.  | Description                | Unit   | Parameters recorded at 200<br>KW (80% rated load)<br>250 KW DA |  |  |  |
|-------|----------------------------|--------|--|--|--|--|
|       | Description                |        |  |  |  |  |
| (i)   | Max sustained Load         | kW     | 200  |  |  |  |
| (ii)  | RPM                        | RPM    | 1488   |  |  |  |
| (iii) | Lub oil Pressure           | Kg/cm² | 2.7  |  |  |  |
| (iv)  | Sea water Pressure         | Kg/cm² | 1.1  |  |  |  |
| (v)   | Lub oil Temperature        | °C     | 98   |  |  |  |
| (vi)  | Fresh water<br>Temperature | °C     | . 85   |  |  |  |
| (vii) | Exhaust Temperature        | °C     | 452  |  |  |  |

(c) <u>Vibration Trials</u>. Vibration trials of DA was undertaken at load 150 kW (60% of rated load) and 200 kW (80% of rated load). Overall vibration readings of DA at monitoring points found within permissible limit and is **Sat**. The details of trials are as follows:-

| Ser   | Description   | 250 KW DA  At 60 % load |             |     | 250 KW DA  At 80 % load |             |     | Remarks<br>(Limit 16<br>mm/sec) |
|-------|---------------|-------------------------|-------------|-----|-------------------------|-------------|-----|---------------------------------|
|       |               | )<br>H                  | 150 KW<br>V | A   | (/<br>  H               | 200 KV<br>V | Α   |                                 |
| (i)   | Engine FE     | 5.2                     | 2.8         | 3.4 | 5.7                     | 3.6         | 3.5 | Sat                             |
| (ii)  | Engine DE     | 4.4                     | 4.5         | 3.2 | 4.5                     | 5.7         | 3.3 | Sat                             |
| (iii) | Alternator DE | 9.0                     | 5.9         | 7.1 | 10.3                    | 7.1         | 7.5 | Sat                             |
| (iv)  | Alternator FE | 5.2                     | 3.4         | 4.2 | 6.2                     | 4.3         | 4.8 | Sat                             |

## (d) Attenuation checks.



|          | 150 KW (60 % load) |     |     |     |     |     | 200 KW (80 % load) |     |     |      |     |     |
|----------|--------------------|-----|-----|-----|-----|-----|--------------------|-----|-----|------|-----|-----|
| Position | 1                  | 2   | 3   | 4   | 5   | 6   | 1                  | 2   | 3   | 4    | 5   | 6   |
| Тор      | 5.8                | 5.0 | 6.4 | 9.4 | 4.5 | 5.9 | 7.9                | 5.1 | 7.7 | 10.2 | 5.2 | 6.8 |
| Bottom   | 1.6                | 0.5 | 1.1 | 2.5 | 0.4 | 1.4 | 1.2                | 0.8 | 2.3 | 2.2  | 0.7 | 2.2 |
| Atten.   | 72                 | 90  | 82  | 73  | 91  | 76  | 84                 | 84  | 70  | 78   | 86  | 70  |
| Remarks  | SAT                |     |     |     |     |     |                    |     |     |      |     |     |

**Note:** Attenuation lesser than 70% indicates overloaded/over tightened mounts. All SV mounts to be loosened and torque tightened as per OEM specified values.

## (e) SPM Readings.

| Ser. | Description       |         | 0% Load<br>dbm/ dbc | 60 % Load<br>dbm/ dbc | 80 % Load<br>dbm/ dbc | Remarks |  |
|------|-------------------|---------|---------------------|-----------------------|-----------------------|---------|--|
| (a)  | Alternator<br>End | Driven  | 16/08               | 20/12                 | 19/07                 | SAT     |  |
| (b)  | Alternator Fi     | ree End | 14/04               | 16/05                 | 19/04                 | SAT     |  |